

INQUIRY SHEET OF EMBA

No. 序号	Item name 项目名称	Content provisions 内容规定						
11. 4	Inquiry company information 询价公司信息	Company name:EMBA Elektrik Uretim A.S.(Hunutlu Power Plant) 公司名称: EMBA Elektrik Uretim A.S.(Hunutlu Power Plant)						
		Address:Şefik Sokak No.5 34330 Levent-Beşiktaş İstanbul 地址: Şefik Sokak No.5 34330 Levent-Beşiktaş İstanbul						
1		Hunutlu Power Plant Address: Akyuva district, EMBA Cluster House No.1, Yumurtalik, Adana, Turkey 胡努特鲁发电厂地址: Akyuva district, EMBA Cluster House No.1, Yumurtalik, Adana, Turkey						
		Phone:+90 5393048227【Ms. HUANG】huangxiaoxiao@embapower.com 联系电话: +90 5393048227【Ms. HUANG】huangxiaoxiao@embapower.com						
2	Inquiry subject 询价主题	Installation of removable insulation for condensate flow nozzle pipe of Unit 1 1号机组凝结水流量喷嘴管道可拆卸式保温制作安装						
3	Scope of work and detailed requirements 施工范围和详细要 求	See Annex 1, Technical Requirements, for details 详见附件1《技术要求》						
4	Planned service duration 计划服务期限	22 April 2024 to 30 April 2024 2024年04月22日到2024年04月30日						
5	Location of construction 施工地点	Turkey Hunutlu Thermal Power Plant(Sugözü District, Yumurtalik City, Adana Province, Turkey;						
		Currency of quotation is United States dollars and the price is fixed for the duration of the contract 报价货币为美元,在合同执行期间价格固定不变						
	Quotation requirements 报价要求	The price shall include the stamp duty required to be paid by both parties to the procurement contract (all to be borne by the contractor and to be paid by the contractor at the relevant tax authorities); 价格应包含采购合同双方需要缴纳的印花税(均由承包人承担,并由承包人负责去相关税务部门缴纳);						
6		The quotation includes all the costs of completing the construction content, including but not limited to: labour costs, material costs, machinery costs, labour protection supplies costs, accommodation costs, food and beverage costs, transportation costs (horizontal and vertical transportation inside and outside the plant), risk costs, profits, taxes, and other costs; 报价包含完成施工内容的全部费用,包括但不限于:人工费、材料费、机械费、劳动保护用品费用、住宿费、餐饮费、交通费(厂内和厂外的水平、垂直运输)、风险费、利润、税金,等全部费用;						
7		25 April 2024, by 12 a.m. 2024年4月25日,上午12点之前						
8	Quotation method 报价方式	Submission Method: Email Offers; 报价方式:邮件发送报价; Main send: huangxiaoxiao@embapower.com Cc: HongDequan@embapower.com;zhenchaohou@embapower.com						
9	Price form 价格形式	Fixed lump-sum price, which is fixed for the duration of the contract, without any additional payment by the employer 固定总价,合同执行期间价格固定不变,雇主不额外支付任何其他费用						
10	Settlement method 结算方式 Settlement of accounts after construction is completed and final acceptance is passed 施工完成,通过最终验收后,办理结算							
		No advance payment 无预付款						
11		Completion payments: Upon receipt by the Employer of a VAT invoice from the Contractor that meets the Employer's requirements, payment will be made within 30 working days at 100 per cent of the amount invoiced for Lira, with no quality assurance guarantee 完工款: 雇主收到承包人提供的满足雇主要求的增值税发票后,30个工作日内按照发票里拉金额的100%支付,无质量保证金						
		The exchange rate for the conversion of US dollars into Turkish lira is selected from the foreign exchange buying rates published on the TCMB website in [Indicative Exchange Rates] on the day of the invoice date or the day before the invoice date; 美元折算土耳其里拉的汇率选用发票日期当天或者发票日期前一天,TCMB网站公布的【Indicative Exchange Rates】中的外汇买入汇率;						



INQUIRY SHEET OF EMBA

No.Item nameContent provisions序号项目名称内容规定						
12	Language 语言	English is the official language of this inquiry, and the companies participating in the quotation declare that they fully understand the contents expressed in English in this inquiry announcement. 英语作为本次询价的正式语言,参与报价的公司声明充分理解本询价公告中英语所表达的内容				
	Documents to be sent when quoting 报价时需要发送的 文件	*The Qualification documents issued by the Turkish goverment for for carrying out such supply. *由土耳其政府颁发的进行此类供应的资格文件。				
		*Business license of enterprise legal person; *企业法人的营业执照;				
		*Valid and up-to-date Trade Registry Gazette; *有效的和最新的贸易登记公报;				
12		*Valid and updated Signature Circular; *有效的和更新的签署通知;				
		*Valid and up-to-date Tax Certificate; *有效的和最新的税务证书;				
		*Other documents if necessary. *如有必要,还有其他文件。				
		*Annex 1 Bill of Quantities(Signature and seal). *附件1 BOQ(签名和盖章版本)。				
Thank you for your cooperation, looking forward to your quotation!						



Bill of Quantities Quotation

From:EMBA ELEKTRİK ÜRETİM A.Ş.

No.	ITEM	ITEM DESCRIPTION	UOM	Estimate - Qty.	UNIT PRICE			TOTAL PRICE			
					Excluding VAT	Tax Rate	Including VAT	Excluding VAT	VAT TAX	Including VAT	REMARKS
		Φ457×14 pipe Φ457×14管道	meter	21.00		20.00%	0.000000	0.00	0.000000	0.000000	
2		Φ457×14 Tee Φ457×14三通	pcs	1.00		20.00%	0.000000	0.00	0.000000	0.000000	
	_	DN450 manual gate valve DN450手动闸阀	pcs	3.00		20.00%	0.000000	0.00	0.000000	0.000000	
	TOTAL(Excluding VAT)							0.00	0.00	0.00	
VAT TAX							0.00				
TOTAL(Including VAT)							0.00				

Annex 1 附件 1

1号机组凝结水流量喷嘴管道保温方案

Installation of removable insulation for condensate flow nozzle pipe

of Unit 1

一、技术要求 Technical Requirements:

- 1. 需保温厂家进厂实地测量, 计算;
- 2. 目前系统介质温度 156℃,需厂家设计保温材料,环境温度不高于 27℃时,设备和管道保温结构外表面温度不应超过 50℃,要求保温材料防火、防水,防油,外表可用湿布擦拭,外表颜色以 RAL7038 为主;
- 3. 厂家需提供设计图纸发我方进行会审;
- 4. 厂家负责本次保温设计、材料、施工的全部工作;
- 5. 提供保温原材料热导率、保温溶重试验检测报告;
- 6. 提供保温原材料产品质量证明书、合格证。
- 1. Need insulation manufacturers into the factory field measurements, calculations;
- 2. the current system medium temperature of 156 $^{\circ}$ C, manufacturers need to design insulation materials, ambient temperature is not higher than 27 $^{\circ}$ C, equipment and pipeline insulation structure of the external surface temperature should not exceed 50 $^{\circ}$ C, the requirements of the insulation material fireproof, waterproof, oilproof, the appearance of a wet cloth can be used to wipe the appearance of the colour of the main RAL7038;
- 3. Manufacturers need to provide design drawings sent to us for review;
- 4. The manufacturer is responsible for all the work of this thermal insulation design, material and construction;
- 5. Provide thermal conductivity of insulation raw materials, insulation soluble weight test report;
- 6. Provide insulation raw material product quality certificate, certificate of conformity.

二、保温工作量 Insulation workload:

序号	名称	单位	数量	备注
NO.	NAME	UNIT	QUANTITY	NOTE
1	Φ457×14 管道	米	21	
I I	Ф457×14 ріре	meter	21	
2	Φ457×14 三通	个	1	

	Φ457×14 Tee	pieces		
2	DN450 手动闸阀	台	2	
3	DN450 manual gate valve	pieces	3	